### **U.S. DEPARTMENT OF ENERGY**

## FIELD WORK PROPOSAL

1.	WORK PROPOSAL NO .:	2. REVISION NO.:		3. DATE PREPARED:		
	JLAB-HEP-XX	2		2/06		
4.	WORK PROPOSAL TITLE:		5. BUDGET AI	ND REPORTING CODE:		
	ILC 9-Cell Cavity EP Processin	g and Preparation				
6.	WORK PROPOSAL TERM: Two years					
7.	HEADQUARTERS OFFICE PROGRA	AM MANAGER:	8. HEADQUARTERS ORGANIZATION:			
	Robin Staffin, Assoc. Dir., HEP (3	01) 903-3624	Office of High Energy Physics			
	hep-tech@science.doe.gov					
9.	DOE FIELD ELEMENT WORK PRO	POSAL REVIEWER:	10. DOE FIELI	D ELEMENT:		
	Jim Turi, (757) 269-7146, turi@jla	b.org	Oak Ridge Operations			
11.	CONTRACT WORK PROPOSAL MA	ANAGER:	12. CONTRAC	TOR NAME:		
	Swapan Chattopadhyay, (757)269- swapan@jlab.org	7001	Southeastern U Thomas Jeffer	Universities Research Association, Inc., son National Accelerator Facility (Jefferson Lab)		

13. Work Proposal Description

Principal Investigators: John Mammosser

This work is in support of the FNAL cryomodule fabrication and development plans. This proposal is to perform the necessary steps to process, qualify and prepare eight (8) ILC 9-cell cavities for string assembly at FNAL. Electropolish process development for optimum surface properties will continue in parallel. All procedures and process data will be documented. Fermilab personnel will participate and be trained during this process. Funding for this work will be via MoU from Fermilab.

14. CONTRACTOR WORK PROPOSAL MANAGER		15. OPERATIONS OFFICE REVIEW OFFICIAL			
Signature	Date	Signature	Date		
16. DETAIL ATTACHMENTS	f. Technical Prog g. Future Accom x h. Relationships i. NEPA Projects j. Milestones	gress <u>x</u> plishments <u></u> to Other Projects <u></u> s	<ul> <li>k. Deliverables</li> <li>l. Performance measures/expectations</li> <li>m. ES&amp;H Considerations</li> <li>n. Human/Animal Subjects</li> <li>o. Other (Specify)</li> </ul>		

# WORK PACKAGE REQUIREMENTS FOR OPERATING/EQUIPMENT OBLIGATIONS AND COSTS

CONTRACTOR NAME: Southeastern Universities Research Association Thomas Jefferson National Accelerator Facility (Jefferson Lab)	n, Inc.	WORK PROPOSA	AL #:	REV. 1	#:	DATE 2/06	PREPARED:
17 STAFEING (IN STAFE VEARS)	FY 2006 Allocated	FY 2007 Target	FY T	2008 arget	Requ	FY 2 uirements	2007 Authorized
<ul> <li>a. SCIENTIFIC</li> <li>b. OTHER DIRECT</li> <li>c. TOTAL DIRECT</li> </ul>		1.0 1.0 2.0					
18. OPERATING EXPENSE (in thousands)							
a. TOTAL OBLIGATIONS (B/A)		425					
b. TOTAL COSTS (B/O)		425					
<ul><li>19. EQUIPMENT (in thousands)</li><li>a. EQUIP OBLIGATIONS (B/A)</li><li>b. EQUIPMENT COSTS (B/O)</li></ul>							
20. MILESTONE SCHEDULE (Tasks)		Dates		Proposed S	<u>\$</u>	<u>A</u> 1	uthorized \$
8 Cavities Processed and Shipped		10/07		425			
21. REPORTING REQUIREMENTS (De Quarterly reporting	escription):	· · · · · ·					

TITLE:	BUDGET AND REPORTING CODE	DATE PREPARED		
ILC CRYOMODULE VALUE ENGINEERING		7/05		
WP NUMBER	CONTRACTOR NAME:			
JLAB-HEP-XX	Southeastern Universities Research Association, Inc., Thomas Jefferson National Accelerator Facility (Jefferson Lab)			

#### 16. c. <u>Purpose</u>

This work is to process, qualify and prepare eight (8) ILC 9-cell cavities for string assembly at FNAL. This string is intended for the second type 4 cryomodule to be assembled at Fermilab. Electropolish process development for optimum surface properties will continue with the aim of achieving 35 MV/m performance. This work is a continuation of FY06 activities funded by MOU with Fermilab.

#### 16. e. Approach

- Cavity Qualification: These cavities will be tuned to frequency, chemically treated be means of electropolish, high pressure rinsed and dried, assembled in Class 10 cleanroom, and RF qualified at cryogenic temperatures in vertical dewar. Best procedures will be implemented and performance will be best effort towards the goal of 35MV/m. RF test cycles will be repeated as necessary to obtain best performance under given timeline and funding.
- Addition of the Helium Vessel: The helium vessels will be received from FNAL, mechanically inspected, cleaned, assembled and welded to the cavities.
- Input coupler: The input coupler will be cleaned and assembled to the cavity in Class 10 conditions and the cavities shipped to FNAL.

## 16. h. <u>Relationships to Other Projects</u>

This work is in support of Fermilab's ILC project, specifically the fabrication of a type 4 cryomodule to be installed in the SMTF. Electropolish procedures developed during this work will be made available to Fermilab for possible implementation in an industrial facility for large-scale production in the future. This project is complementary to the university based proposal for detailed understanding and development of the electropolish method for niobium.

## 16. k. Deliverables

8 ILC-style cavities with helium vessels, electropolished, dressed and with FPC assembled. EP process parameters and documentation.